

Exterior Porch and Stairs Estimate Geometry Worksheet

Project: Front Porch and Entry Stairs Maintenance Repaint

Property: 10375 SW Dunlin Pl, Beaverton, OR 97007

Prepared: 2026-08-25

Status: Photo-based takeoff; field verification required before scheduling.

Scope and Evidence

Included gray surfaces are the porch floor, stair tread tops, and tread nosings. Included white surfaces are the stair risers, stair railings, porch guardrail, balusters, posts, and caps. Stringer faces, deck rim, lattice, ceiling, house surfaces, door, concrete, undersides, and framing are excluded.

The ten supplied photographs were reviewed at full resolution. Counts labeled **direct** can be followed through the current stair photographs. Dimensions labeled **inferred** use nominal board widths, typical railing spacing, the 36-inch entry door, and repeated components as scale references.

Count and Dimension Audit

Item	Working value	Evidence and confidence
Porch length	10.0 ft	Inferred; door and railing proportions support 9-11 ft
Porch depth	4.25 ft	Inferred; approximately nine nominal 2x6 board modules across; 4.0-4.5 ft
Porch floor	42.50 sq ft	10.0 x 4.25; no stair-opening deduction
Stair clear width	3.5 ft	Inferred from door/riser proportions; 3.25-3.75 ft
Tread tops	9	Direct count in full-run and oblique stair views
Risers	10	Direct/derived: ten vertical rises, including one raw replacement riser
Tread walking depth	11.25 in	Direct construction pattern: two nominal 2x6 boards plus gap
Stair rail length	10.0 ft each side	Inferred from 9 tread runs and approximately 6 ft rise; 9.5-10.5 ft
Porch guardrail	13.0 linear ft	Inferred from visible front section and returns; 11-15 ft
Combined rail	33.0 linear ft	20.0 ft stair + 13.0 ft porch; 31-35 ft
Balusters	56	Visible sections counted where clear; concealed sections inferred from repeated spacing; 50-62
Posts	6	Two lower stair posts, two upper stair/porch posts, two porch/end posts; direct plus partially obscured inference

Porch floor

The deck boards run along the porch length. Approximately nine board-and-gap modules span the depth:

9 modules x approximately 5.67 in = 51.0 in = 4.25 ft

Porch floor = 10.0 ft x 4.25 ft = 42.50 sq ft

The stairs meet the outside edge of the landing. The photographs do not show a rectangular floor opening extending into the porch, so **no stair-head deduction is taken**.

Stairs

Tread tops = 9 x 3.5 ft x 0.9375 ft = 29.53 sq ft
Tread nosings = 9 x 3.5 ft x 0.125 ft = 3.94 sq ft
Risers = 10 x 3.5 ft x 0.5208 ft = 18.23 sq ft
Raw replacement riser subset = 1 x 3.5 ft x 0.5208 ft = 1.82 sq ft

Rail members

The rail girth model covers the exposed faces/edges of the cap, sub-rail, and bottom rail. It remains **2.209 sq ft per linear foot** of assembled railing.

Stair rails = 2 x 10.0 ft = 20.0 linear ft
Porch guardrail = 13.0 linear ft
Combined rail = 33.0 linear ft
Rail-member area = 33.0 x 2.209 = 72.90 sq ft

Balusters

The photographs do not expose every baluster in one view. Clear sections were counted, then obscured sections were extended using the repeated approximately 5.5-inch on-center module. The resulting working count is 56, within the visual 50-62 range.

Baluster girth = 4 x 1.5 in = 0.500 ft
Exposed length = 27 in = 2.25 ft
Baluster area = 56 x 0.500 ft x 2.25 ft = 63.00 sq ft

Posts and caps

Six posts are carried: two lower stair posts, two upper stair/porch posts, and two porch/end posts. Working exposed shaft length is 20 ft total.

Post shaft area = 20.0 ft x 1.1667 ft girth = 23.33 sq ft
Six caps = 6 x 0.55 sq ft = 3.30 sq ft
Posts and caps = 26.63 sq ft

Included Physical Takeoff

Each component is counted once, regardless of the number of coating applications.

Component	Gray sq ft	White sq ft	Total sq ft
Porch floor	42.50	-	42.50
Nine tread tops	29.53	-	29.53
Nine tread nosings	3.94	-	3.94
Ten risers	-	18.23	18.23
Rail members	-	72.90	72.90
56 balusters	-	63.00	63.00
Six posts and caps	-	26.63	26.63
Included total	75.97	180.76	256.73

Reconciliation: 75.97 gray + 180.76 white = **256.73 sq ft included one-coat physical area.**

Coating Demand

Coating demand is calculated separately from physical area.

Operation	Demand
Gray localized preparation allowance (about 25% of gray area)	~19.0 sq ft treated
One complete tinted gray primer coat	75.97 sq ft
One complete gray finish coat	75.97 sq ft
White localized preparation	Actual failures and repairs only
White spot primer: raw riser plus approximately 10% of remaining white area	~19.7 sq ft
One complete white finish coat	180.76 sq ft
Total liquid-coating coverage demand	352.40 sq ft

The total consists of **151.94 sq ft gray coating demand** (primer plus finish) and **200.46 sq ft white coating demand** (spot primer plus finish).

Purchase Quantities

Product	Theoretical use	Purchase plan	Expected remainder
Tinted gray-compatible exterior primer	approximately 0.25 gal	1 gallon	Substantial usable remainder
Gray porch-and-floor finish	approximately 0.25 gal	1 gallon	Substantial usable remainder
White exterior finish	approximately 0.55-0.65 gal after detail loss	1 gallon	Usable touch-up remainder
Compatible white spot primer	less than 0.1 gal	1 quart or compatible stock	Usable remainder

The smaller geometry reduces theoretical use but does not eliminate the need for separate products. One container of each gray product and white finish is still the practical purchase minimum; the white primer can be a quart or compatible stock. Leftover material remains usable and should be labeled.

Field Verification Checklist

- Measure porch length and board-module depth.
- Confirm nine tread tops, ten risers, and stair width.
- Measure both stair rails and all porch guardrail sections.
- Count every baluster and post, including obscured porch sections.
- Confirm stringers, rim, lattice, ceiling, undersides, and framing remain excluded.
- Confirm coating compatibility, moisture limits, colors, and alternate-entry plan.