

Exterior Paint Estimate Geometry Worksheet

Property: 2201 NE 58th Ave, Portland, OR 97213

Front Elevation

Known Dimensions

- Front width: 27 ft
- Front gable centered over porch
- Covered front porch included in scope
- Aluminum siding

Body Siding Calculation

Main Wall Area

Front wall width: 27 ft

Assumed eave height: 8 ft

Gross wall area:

$$27 \text{ ft} \times 8 \text{ ft} = 216 \text{ sq ft}$$

Opening Deductions

Opening	Estimated Area
Front window (left)	24 sq ft
Front window (right)	24 sq ft
Front entry door	21 sq ft
Total Deductions	69 sq ft

Net rectangular wall area:

$$216 - 69 = 147 \text{ sq ft}$$

Front Gable

Gable width: 27 ft

Estimated gable height above eave: 6.5 ft

Gable area:

$$(27 \text{ ft} \times 6.5 \text{ ft}) \div 2 = 87.75 \text{ sq ft}$$

Rounded:

88 sq ft

Front Body Siding Total

Component	Area
Net Main Wall	147 sq ft
Front Gable	88 sq ft
Total Front Body Siding	235 sq ft

Porch Scope (Separate From Body Siding)

Component	Estimated Area
Porch Ceiling	100 sq ft
Porch Columns	35 sq ft
Porch Fascia / Beam	25 sq ft
Total Porch Scope	160 sq ft

Notes

- Front porch ceiling exhibits significant paint failure and peeling.
- Porch ceiling likely requires extensive scraping and spot priming.
- Window trim and door trim included in trim scope.
- Body siding is aluminum.
- Brick foundation excluded from paint scope.

Confidence

Medium

Front width is confirmed from field measurements. Wall height and gable height remain estimated pending full elevation reconciliation.

Right Elevation

Known Dimensions

- Right side width: 25 ft
- Full-height side gable
- Large masonry chimney (excluded from paint scope)
- Aluminum siding

Body Siding Calculation

Main Wall Area

Side width: 25 ft

Assumed eave height: 8 ft

Gross wall area:

$25\text{ ft} \times 8\text{ ft} = 200\text{ sq ft}$

Opening Deductions

Opening	Estimated Area
Small lower window	6 sq ft
Large upper window	24 sq ft
Gable vent	2 sq ft
Total Deductions	32 sq ft

Net rectangular wall area:

$200 - 32 = 168\text{ sq ft}$

Right Side Gable

Gable width: 25 ft

Estimated gable height above eave: 8 ft

Gable area:

$$(25 \text{ ft} \times 8 \text{ ft}) \div 2$$

$$= 100 \text{ sq ft}$$

Chimney Deduction

Visible chimney width appears approximately 3.5–4 ft.

Paintable siding hidden behind chimney estimated at:

$$4 \text{ ft} \times 14 \text{ ft}$$

$$= 56 \text{ sq ft}$$

Deduct:

$$56 \text{ sq ft}$$

Right Body Siding Total

Component	Area
Net Main Wall	168 sq ft
Gable Area	100 sq ft
Subtotal	268 sq ft
Chimney Deduction	-56 sq ft
Total Right Body Siding	212 sq ft

Trim Scope (Separate)

Component	Estimated Quantity
Window Trim	2 windows

Gable Trim	25 linear ft
Corner Trim	2 corners
Fascia / Rake Trim	Included in trim scope

Notes

- Large brick chimney significantly reduces paintable siding area.
- Chimney itself excluded from painting scope.
- Upper gable window trim included.
- Lower window trim included.
- Gable vent excluded from paint quantity.
- Aluminum siding in generally serviceable condition.

Confidence

Medium-High

Right elevation width is supported by field measurements. Chimney deduction remains estimated from imagery and should be verified during final reconciliation.

Rear Elevation

Known Dimensions

- Rear width: 33 ft
- Rear is wider than front due to bump-out / projection geometry
- Front width comparison: 27 ft
- Added rear width: $33\text{ ft} - 27\text{ ft} = 6\text{ ft}$
- Rear includes multiple wall planes rather than one flat elevation
- Aluminum siding
- Rear deck / rear entry included in access and trim considerations

Geometry Notes

The rear elevation should not be treated as one perfectly flat 33 ft wall.

For estimating purposes, model it as:

1. Main rear wall plane
2. Rear-right projecting gable / door section
3. Rear-left wall section

4. Small return walls created by bump-outs

The 33 ft rear width is used as the total rear-facing width, while the bump-out returns are accounted for separately where visible.

Body Siding Calculation

Main Rear Wall Area

Rear width: 33 ft

Assumed eave height: 8 ft

Gross rear wall area:

$$33 \text{ ft} \times 8 \text{ ft} = 264 \text{ sq ft}$$

Rear Gable Area

The main rear gable appears over the projecting rear door section.

Estimated gable base: 12 ft

Estimated gable height above eave: 6.5 ft

Gable area:

$$(12 \text{ ft} \times 6.5 \text{ ft}) \div 2 = 39 \text{ sq ft}$$

Bump-Out / Return Wall Allowance

The rear has offset wall planes and return sections from the bump-out geometry.

Allowance:

$$6 \text{ ft return} \times 8 \text{ ft height} = 48 \text{ sq ft}$$

Use:

$$48 \text{ sq ft}$$

Opening Deductions

Opening	Estimated Area
Rear French doors	36 sq ft
Rear-left window	12 sq ft
Rear-center/side window	12 sq ft
Small basement/lower opening	6 sq ft
Total Deductions	66 sq ft

Rear Body Siding Total

Component	Area
Main Rear Wall	264 sq ft
Rear Gable	39 sq ft
Bump-Out / Return Allowance	48 sq ft
Subtotal	351 sq ft
Opening Deductions	-66 sq ft
Total Rear Body Siding	285 sq ft

Trim Scope (Separate)

Component	Estimated Quantity
Rear French Door Trim	1 large door set
Window Trim	2–3 windows
Gable / Rake Trim	1 rear gable
Corner Boards	Multiple due to bump-outs
Rear Deck / Entry Trim	Included in trim scope

Notes

- Rear is more complex than the front due to multiple offsets and wall returns.
- Rear deck may affect access and prep time.
- Rear gable should be included, but its base appears narrower than full rear width.
- Vegetation and deck railings may reduce access.
- Brick/concrete/foundation areas excluded from body siding.
- Aluminum siding body area only; trim and porch/deck components tracked separately.

Confidence

Medium

Rear total width is supported by field measurement. Exact bump-out wall returns and rear gable base are estimated from imagery and should be verified if higher precision is needed.

Left Elevation

Known Dimensions

- Left side main depth: 25 ft
- Additional bump-out / return section: approximately 3 ft
- Working left elevation length: 28 ft
- This is the side visible along the bottom of the satellite view
- Aluminum siding
- Large full-height gable face
- Rear-side entry / deck area connects into this side

Geometry Notes

The left elevation is not a simple 25 ft flat wall.

For estimating purposes, model it as:

1. Main left wall plane: 25 ft
2. Small bump-out / return section: approximately 3 ft
3. Large gable face above the main wall
4. Multiple windows and utility penetrations
5. Rear-side door area treated separately in trim/access scope

Body Siding Calculation

Main Wall Area

Working wall length: 28 ft

Assumed eave height: 8 ft

Gross main wall area:

$$28 \text{ ft} \times 8 \text{ ft} = 224 \text{ sq ft}$$

Left Side Gable

Gable base: 25 ft

Estimated gable height above eave: 8 ft

Gable area:

$$(25 \text{ ft} \times 8 \text{ ft}) \div 2 = 100 \text{ sq ft}$$

Opening Deductions

Opening	Estimated Area
Large upper window	24 sq ft
Lower left window	12 sq ft
Lower center/right window	12 sq ft
Rear-side door/window area	18 sq ft
Small gable vent	2 sq ft
Total Deductions	68 sq ft

Left Body Siding Total

Component	Area
Main Wall Area	224 sq ft
Left Gable Area	100 sq ft

Subtotal	324 sq ft
Opening Deductions	-68 sq ft
Total Left Body Siding	256 sq ft

Trim Scope (Separate)

Component	Estimated Quantity
Window Trim	3–4 windows
Door Trim	1 rear-side door
Gable / Rake Trim	1 large gable
Corner Boards	Multiple due to bump-out
Utility Penetrations	Meter / conduit / cable areas
Rear Deck / Stair Rail Obstruction	Access consideration

Notes

- This side has more wall height and gable area than the front.
- Utility lines, meter, conduit, and deck railings may slow prep and painting.
- Window bases show peeling/failure and should be scraped and painted.
- Rotted window base sections should be repaired with bondo where appropriate.
- Aluminum siding body area only; trim and repair work are tracked separately.
- The 3 ft bump-out is included as an allowance in wall length.

Confidence

Medium

The 25 ft main side length is supported by field measurement. The additional 3 ft bump-out and opening deductions are estimated from imagery and should be verified if final precision is needed.